### A. Alfred Taubman Health Sciences Library Renovation



#### **Project Description**

A renovation of approximately 137,000 gross square feet of space to create a smaller library collection, increased health sciences instructional space including a clinical skills and simulation suite, and spaces for computing, study, and faculty and student services. A 6,000-gross-square-foot addition will be constructed to improve vertical circulation

#### **Energy Efficiency Measures**

- The building's design and systems include a number of energy efficient features that allow for an estimated energy savings of 30% when compared with a code energy compliant building as defined in ASHRAE 90.1-2007 Appendix G
- High Performing Envelope including glazing with low-e coatings to reduce thermal losses in the winter and radiation gain in the summer
- Exterior sun-shading devices on the south facing elevation to minimize solar heat gain on sunny days
- Enthalpy Wheel allows return air to condition outside air which reduces heating/cooling load in the air handling unit
- Chilled Beams use chilled water as a cooling medium which reduces ductwork, shafts, and air handling unit size
- HVAC controls prevent simultaneous heating and cooling and occupancy sensors control temperature
- · Efficient light fixtures and occupancy sensors reduce energy use

#### **Other Sustainability Features**

- This project is LEED® certified to the Gold level and achieved 67 points under the LEED for New Construction v2009 rating system.
- Project site located near public and U-M bus routes to encourage use of public transit
- Close proximity to basic services such as banks and restaurants to encourage building occupants to walk instead of drive
- Landscaping is made of native and adaptive plantings and does not require permanent irrigation
- Designed for a 38% water consumption savings beyond Michigan Plumbing Code; savings will be
  obtained via use of dual flush water closets, 1/8 gallon flush urinals, and automatic sensor operated
  faucets
- Building reuse of approximately 90% of existing walls, floors and roof
- Over 25% of materials used contain recycled content
- Over 35% of materials used were extracted and manufactured within 500 miles of the project site
- Low-VOC paints, flooring, composite wood, adhesives and sealants
- 88% of demolition and construction waste diverted from landfill

Print Date: 04/04/2018 Last Updated: 03/26/2018

# A. Alfred Taubman Health Sciences Library Renovation **Project Data**

Budget: \$55 M

Schedule: Completion Scheduled for Fall 2015 137,000 gross sq. ft. renovation Square Feet:

6,000 gross sq. ft. addition

## **Substantially Complete: June 2015**

Project Status: Substantial Completion

Design Complete: 100%

Construction Complete: 100%

Print Date: 04/04/2018 files (x86)\christiansteven\crd\Cache\sustainability{528289316}.rpt Page 2 of 2 Last Updated: 03/26/2018