



A MIN DEPTH OF 1". TOTAL DEPTH OF CONTROL JOINT MUST BE 1/4 OF SLAB THICKNESS. IF SAWCUT IS REQUIRED TO MEET THIS DEPTH, IT MUST BE COMPLETED WITHIN 24 HOURS AFTER HAND TOOLING. 8" THICK 4000 PSI CONCRETE W/FIBERMESH

6" MDOT CL II GRANULAR MATERIAL COMPACTED TO 98% OF MAXIMUM DENSITY

COMPACTED SUBGRADE

## **SIDEWALK - 8" THICKNESS**

NOTES: EXPANSION JOINTS SHALL BE INSTALLED SUCH THAT NO SINGLE DIMENSION EXCEEDS 50 FT. AREA BETWEEN EXPANSION JOINTS NOT TO EXCEED 320 SQ.FT.

> 1/2" EXPANSION PAPER SHALL BE PLACED AT ALL LOCATIONS WHERE NEW SIDEWALK ABUTS CONCRETE CURB, EXISTING SIDEWALK, LIGHT POLE BASES AND RETAINING WALLS.

SNAP-CAP EXPANSION JOINT STRIPS CAN BE USED ON ALL EXPANSION JOINTS.

ALL EXPANSION JOINTS SHALL BE SEALED.

BROOM FINISH PARALLEL TO JOINTS AND PERPENDICULAR TO TRAFFIC (IF BROOMING PATTERN NOT SHOWN).