PROVIDE 1/2" SMOOTH STAINLESS STEEL DOWELS, 1'-0" LENGTH @ 2' SLEEVED ON ONE END WITH VOID FOR EXPANSION.

CONCRETE BAND

SLAG SAND SETTING BED

4" X 8" PRECAST CONCRETE PAVERS SET IN SLAG SAND SETTING BED, HAND TIGHT JOINTS SAND SWEPT

2 3/8"

1"

6"

6"

PROVIDE 1/2" SMOOTH STAINLESS STEEL DOWELS, 1' LENGTH @ 2' O.C., SLEEVED ON ONE END WITH VOID FOR EXPANSION

EXPANSION JOINT

2"0 DRILLED DRAIN, 5'-0" O.C. - FILL WITH PEASTONE.

6" 4000 PSI CONC. WITH FIBER MESH

FILTER FABRIC

COMPACTED MDOT CLASS II GRANULAR MATERIAL COMPACTED 98% OF MAX DENSITY

COMPACTED SUBGRADE PRIOR TO STONE INSTALLATION

# PRECAST PAVER ON CONCRETE BASE

NO SCALE

SD-PAVER-PRECAST_CONC